

कार्यालय जोधपुर नगर निगम, दक्षिण

क्रमांक:-विकास/दक्षिण/2022-23/1455

दिनांक :- 10/2/2023

—:: अल्पकालीन निविदा सूचना::—

(यू.बी. संख्या.....)

नगर निगम जोधपुर की ओर से निम्नलिखित कार्य हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागों/स्वायत्तशासी/निगमों/बोर्डों/राजकीय उपक्रमों में पंजीकृत ए. ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में मुहरबन्द निविदाएं आमंत्रित की जाती है। निविदा दिनांक 17.2.2023 को 12.30 बजे तक बेची जाकर दिनांक 17.2.2023 को दोपहर 2.00 बजे तक प्राप्त कर 3.00 बजे उपस्थित संवेदको के समक्ष खोली जायेगी। अन्य विवरण एवं शर्तें निविदा प्रपत्र कार्यालय समय में कार्यालय में देखे जा सकते हैं। sppp.raj.nic.in एवं जोधपुर नगर निगम की वेबसाइट urban.rajasthan.gov.in/mcjs पर देखी जा सकती है।

क्र. सं.	कार्य का नाम	अनु. लागत (राशि लाखों में)	घरोहर राशि	निविदा शुल्क	कार्य पूर्ण करने की अवधि
01	Development and other work at Gandhi maidan jodhpur	4.98	9,960/-	500/-	1 माह
02	Construction of Bathroom and other work at Gandhi maidan	4.98	9,960/-	500/-	1 माह

नोट :- (1) कार्य शुरू करने से पूर्व व कार्य पूर्ण करने के पश्चात् कार्य स्थल की फोटो/ विडियोग्राफी सी.डी. आवश्यक रूप से प्रस्तुत करें। (2) सशर्त निविदा स्वीकार नहीं होगी। (3) दोष निवारण अवधि नियमानुसार होगी। (4) घरोहर राशि के डिमाण्ड ड्राफ्ट की वैधता निविदा खोलने की तारीख से निविदा की वैधता अवधि तक होनी अनिवार्य है अन्यथा निविदा कॉपी निरस्त की जा सकती है। (5) निविदा कॉपी बाबत आवेदन पत्र के साथ पंजीयन प्रमाण-पत्र संलग्न करना आवश्यक है, अन्यथा निविदा कॉपी जारी नहीं की जायेगी। (6) आयुक्त नगर निगम जोधपुर के आदेश क्रमांक 9836 दिनांक 07.02.2020 एवं 9975 दिनांक 14.07.2020 के अनुसार पंजीयन रिव्यू आदेश के तहत निविदा स्वीकार/अस्वीकार की जायेगी। (7) श्रीमान् निदेशक, स्वायत्त शासन विभाग राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.2021 की पालना में वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर.टी.पी.पी. नियम 2013 में Additional Performance Security के लिए नियम 75 -ए के अनुसार Additional Performance Security जमा करवानी होगी।

2-
आयुक्त

जोधपुर नगर निगम दक्षिण

दिनांक:- 10/2/2023

क्रमांक:- 1456 to 1462

प्रतिलिपी :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. श्रीमान जिला कलेक्टर महोदय, जोधपुर।
2. निदेशक/अधीक्षण अभियन्ता, स्थानीय निकाय विभाग, जयपुर।
3. अधीक्षण अभियन्ता/अधिशासी अभियन्ता, सा.नि.वि./जोधपुर विकास प्राधिकरण जोधपुर।
4. लेखाधिकारी, जोधपुर नगर निगम दक्षिण।
5. उक्त निविदा सूचना दैनिक प्रतिनिधि को वास्ते नियमानुसार समाचार पत्र में प्रकाशन हेतु।
6. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि ई-निविदा सूचना urban.rajasthan.gov.in/mcjs एवं sppp.rajasthan.gov.in, पर अपलोड करें।
7. सूचना पट्ट जोधपुर नगर निगम दक्षिण।

2-
आयुक्त

जोधपुर नगर निगम दक्षिण

NAGAR NIGAM JODHPUR SOUTH

"G" SCHEDULE

Name of work : Development & Other works at Gandhi Maidan Jodhpur

No	Item No.	Particulars	Qty.	Unit	Rate	Amount
1	R-25.1.1 25.2	Random rubble masonry with hard stone in superstructure above plinth level and upto two stories. : Cement mortar 1:6 (1 cement : 6 coarse sand)	45.00	Cum	5135.00	231075.00
2	R-32.3.2	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/coarse sand)	200.00	Sqm	283.50	56700.00
3	R-32.22.1	Pointing on stone, work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing	350.00	Sqm	205.00	71750.00
4	R-30.25.1	Kota stone slab flooring 25mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : Area of each slab 900 to 2000 sqcm	27.00	Sqm	1299.00	35073.00
	R-36.24	Providing and fixing white vitreous china squatting plate urinal with integral rim longitudinal flush pipe.	4.00	Nos	2635.00	10540.00
	R-36.3.1	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	2.00	Nos	5930.00	11860.00
	R-34.15.2	Providing and fixing brass bib cock of approved quality : 20 mm nominal bore	8.00	Nos	377.50	3020.00
	R-34.5.1	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15 mm nominal bore	6.00	Nos	509.00	3054.00

Item No.	Particulars	Qty.	Unit	Rate	Amount
R-36.7.1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require : White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps.	2.00	Nos	2620.00	5240.00
R-1.1.2	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth for 5 Km.	285.00	Cum	245.95	70095.75
	Total				498407.75


Executive Engineer, (South)
Nagar Nigam Jodhpur

Note
 कार्य की दोष निवारण (Defect Liability) अवधि कार्य पूर्णता के पश्चात पांच वर्ष तक रहेगी।
 सशर्त निविदा स्वीकार नहीं होगी।
 कार्य स्थल पर कार्य सम्बन्धित सूचना दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
 कार्य प्रारम्भ करने से पूर्व की कार्यस्थल के फोटोग्राफ/विडियोग्राफी लेकर कार्यालय में जमा करवाना आवश्यक होगा।
 कार्य पूर्ण करने के पश्चात पूर्ण कार्य के फोटोग्राफ/विडियोग्राफी भी जमा करवाने होंगे।
 सभी प्रकार के कर संवेदक को वहन करने होंगे।
 जी-शेड्यूल के आईटम की दर में या अन्य कोई भी टंकण त्रुटि रहने पर फाईनल बी.एस.आर. ही मान्य होगी।
 संवेदक द्वारा कार्यस्थल की सुरक्षा की व्यवस्था स्वयं को करनी होगी।
 कार्य में दोष निवारण अवधि नियमानुसार रहेगी।

We agree to execute the above work @% above/below (in figure)

in word% above/below

of the 'G' Schedule rates & we agree to abide by general & special conditions of the contract

Signature of Contractor


Executive Engineer, (South)
Nagar Nigam Jodhpur

NAGAR NIGAM JODHPUR SOUTH

"G" SCHEDULE

Name of work : Construction of Bathroom & Other works at Gandhi Maidan

S.No	Item No.	Particulars	Qty.	Unit	Rate	Amount
1	R-4.10.1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.	20.00	Cum	210.50	4210.00
2	R-21.1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	20.00	Cum	4340.00	86800.00
3	R-25.1.1	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	74.00	Cum	4245.00	314130.00
4	R-25.12.1.2	Stone work in plain ashlar in super structure upto floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) including pointing with cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade : White sand stone	0.20	Cum	44400.00	8880.00
5	R-31.61.2	Stone slab roofing on ground floor with fine grained stone slab 90mm average thickness from approved quarry including filling of joints slab in cement sand mortar 1:4 with ceiling pointing in cement sand mortar 1 : 3 complete as per specification for span: Above 2.00 metre and up to 2.50 metre	15.00	Sqm	1225.00	18375.00
	R-34.7.2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall	50.00	Mtr	282.00	14100.00
	R-27.11	Providing and fixing 1st quality standard white, grey, ivory, fume red brown, light green, light blue and other light shades glazed tiles confirming to IS : 13753 & IS :15622 of size 200mm x 300mm in walls, floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (excluding the cost of cement plaster on walls and pillar).	50.00	Sqm	837.00	41850.00

S.No	Item No.	Particulars	Qty.	Unit	Rate	Amount
8	S-3.20	P&F rigid PVC pipe fittings (IS: 4985 mark) of approved quality /make including joining the pipe with solvent cement rubber ring and lubricant:				
	3.20.13	a) Socket plug, 110mm				
	320.9	b) Bend 87.5, 110mm	11.00	Nos	81.00	891.00
	3.20.25	c) S-Trap, 110mm	4.00	Nos	162.00	648.00
	3.20.3	d) Plain Tee, 110mm	8.00	Nos	544.00	4352.00
	3.20.13	e) Socket plug, 75mm	8.00	Nos	191.00	1528.00
	320.9	f) Bend 87.5, 75mm	8.00	Nos	68.00	544.00
	3.20.3	g) Plain Tee, 75mm	8.00	Nos	100.00	800.00
	3.20.2	h) Reducer 110x75mm	4.00	Nos	116.00	464.00
		Total	5.00	Nos	100.00	500.00
						498072.00


Executive Engineer, (South)
Nagar Nigam Jodhpur

Note

कार्य की दोष निवारण (Defect Liability) अवधि कार्य पूर्णता के पश्चात पांच वर्ष तक रहेगी।

- सशर्त निविदा स्वीकार नहीं होगी।
- कार्य स्थल पर कार्य सम्बन्धित सूचना दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
- कार्य प्रारम्भ करने से पूर्व की कार्यस्थल के फोटोग्राफ/विडियोग्राफी लेकर कार्यालय में जमा करवाना आवश्यक होगा।
- कार्य पूर्ण करने के पश्चात पूर्ण कार्य के फोटोग्राफ/विडियोग्राफी भी जमा करवाने होंगे।
- जी-शिड्यूल में मदवार दरे मान्य नहीं होगी। जी. सारणी पर प्रतिशत एबाऊ (Above) अथवा बिलो (Below) दरे ही मान्य होगी।
- सभी प्रकार के कर संवेदक को वहन करने होंगे।
- जी-शिड्यूल के आईटम की दर में या अन्य कोई भी टंकरण त्रुटि रहने पर फाईनल बी.एस.आर. ही मान्य होगी।
- संवेदक द्वारा कार्यस्थल की सुरक्षा की व्यवस्था स्वयं को करनी होगी।
- कार्य में दोष निवारण अवधि नियमानुसार रहेगी।

We agree to execute the above work @% above/below (in figure)

In word% above/below
of the 'G' Schedule rates & we agree to abide by general & special conditions of the contract

Signature of Contractor


Executive Engineer, (South)
Nagar Nigam Jodhpur