

जोधपुर नगर निगम, जोधपुर –दक्षिण

क्रमांक:-/विकास/तृतीय/ दक्षिण/2022-23/ 27

दिनांक:- 27/6/2022

:: ई-निविदा सूचना ::

(यू.बी. संख्या.....DLB2223WSOB09570)

नगर निगम दक्षिण जोधपुर की और से निम्नलिखित कार्यो हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागों/स्वायत्तशासी/निगमों/बोर्डों/राजकीय उपक्रमों में पंजीकृत ए.0ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में ई-निविदाएं आमंत्रित की जाती है।

महत्वपूर्ण दिनांकों का विवरण

विवरण	दिनांक
ऑन लाईन निविदा फार्म जमा कराना प्रारम्भ होने की दिनांक व समय	05/7/2022 / 12.30 PM
ऑन लाईन निविदा फार्म जमा कराने की अन्तिम दिनांक व समय	15/7/2022 / 12.30 PM
ऑन लाईन निविदा खोलने की तारीख	15/7/2022 / 3.00 PM
निविदा शुल्क/धरोहर राशि की मूल प्रति अधीक्षण अभियन्ता कार्यालय में जमा कराने की दिनांक व समयावधि	15/7/2022 / 2.00 PM

क्र.सं.	कार्य का नाम	अनुमानित लागत (राशि लाखों में)	धरोहर राशि	निविदा शुल्क	कार्य पूर्ण करने की अवधि
1	Development work at modern toilet Ganeshpura Ward 71	13.75	27,500/-	500/-	4 माह
2.	Development work at park situated in Balaji nagar in Ward 80 (NNJS)	16.00	32,000/-	500/-	4 माह

निविदा की महत्वपूर्ण शर्तें निम्नानुसार है :-

1. निविदा प्रपत्रों को वेबसाईट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदको को निविदा को इलेक्ट्रॉनिक फॉरमेट में वेबसाईट <http://eproc.rajasthan.gov.in> पर जमा करानी होगी।

2. निविदा की प्रक्रिया ऑन लाईन होगी।

3. निविदा हेतु पात्र संवेदको की श्रेणी -

किसी भी सीमा तक

रुपये 300.00 लाख तक

रुपये 150.00 लाख तक

रुपये 50.00 लाख तक

रुपये 15.00 लाख तक

- एए श्रेणी, संवेदक

- ए, श्रेणी संवेदक

- बी, श्रेणी संवेदक

- सी, श्रेणी संवेदक

- डी, श्रेणी संवेदक

4. निविदा खोलने की तिथि को किसी कारणवश यदि सम्पूर्ण निविदायें नहीं खोली जा सकती है, तो उसके अगले कार्य दिवस को शेष निविदायें खोलने का कार्य जारी रखा जावेगा।

5. निविदा प्रक्रिया -

कार्य

सडक

अन्य निर्माण कार्य

पोटेशियम असेसमेंट

150 लाख से 500 लाख तक

100 लाख से 200 लाख तक

पोस्ट क्वालीफिकेशन

500 लाख से अधिक तक

200 लाख से अधिक तक

क्र.सं.	शुल्क वितरण	शुल्क	भुगतान का प्रकार	देय
1	निविदा शुल्क	उपरोक्तानुसार	डिमाण्ड ड्रॉफ्ट /	आयुक्त

			बैंकर चैक	जोधपुर नगर निगम दक्षिण
2	धरोहर राशि	उपरोक्तानुसार	डिमाण्ड ड्रॉफ्ट / बैंकर चैक	आयुक्त जोधपुर नगर निगम दक्षिण
3	ई-टेण्डरिंग प्रक्रिया शुल्क	50 लाख एव उपर 1000/- 50 लाख से नीचे 500/-	डिमाण्ड ड्रॉफ्ट / बैंकर चैक	MD RISL, JAIPUR


6. निविदादाता द्वारा निविदा शुल्क, धरोहर राशि एवं प्रक्रिया शुल्क हेतु निम्नलिखित राशि कि मूल प्रति जोधपुर

नगर निगम कार्यालय में नियमानुसार निविदा खोले जाने के समय से पूर्व जमा करवाना आवश्यक है।
निम्नलिखित डिमांड/बैंकर चैक शुल्क ऑनलाइन निविदा फार्म जमाने की अन्तिम तिथि से पूर्व का होना आवश्यक है।

7. निविदा शुल्क/ धरोहर राशि/ ई-निविदा प्रक्रिया शुल्क के डिमाण्ड ड्राफ्ट की वैधता खोलने की तारीख से निविदा की वैधता अवधि तक होनी अनिवार्य है अन्यथा निविदा कॉपी निरस्त की जा सकती।
8. प्रदत्त दरें निविदा खोलने की दिनांक से 90 दिवसों तक निविदा स्वीकृति हेतु मान्य (Vaild) रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है, तो उसकी धरोहर राशि जब्त कर ली जावेगी।
9. यदि संवेदक के नजदीकी रिश्तेदार (प्रथम रक्त सम्बन्धी व उनके पति/पत्नी) कार्य से संबंधित अधीनस्थ कार्यालय में खण्डीय लेखाकार अथवा सहायक अभियन्ता से लेकर अधीक्षण अभियन्ता स्तर का किसी भी स्तर पर पदस्थापित हो, तो उसके कार्य पर नियुक्त करने पर प्रतिबन्ध रहेगा।
10. राज्य सरकार में किसी भी अभियांत्रिकी विभाग में किसी भी इंजीनियर अथवा इंजीनियर या प्रशासनिक कार्य पर नियुक्त राजपत्रित अधिकारी राज्य की अनुमति के बिना सेवा निवृत्ति के 2 वर्ष तक संवेदक अथवा उसके कर्मचारी के रूप में कार्य नहीं कर सकेंगे। यदि संवेदक अथवा उसके कर्मचारियों में कोई ऐसा व्यक्ति जिसने राज्य सरकार की उक्त लिखित अनुमति निविदा जमा कराने से पहले अथवा संवेदक के यहां से सेवाएं लेने से पहले अनुमति नहीं ली है, तो अनुबन्ध रद्द किया जा सकेगा।
11. उक्त आईटम की दोष निवारण अवधि राज्य सरकार द्वारा निर्धारित नोर्म्स के अनुसार होगी।
12. निविदा में निविदादाताओं से अंतर राशि परफोरमेन्स सिक्यूरिटी के रूप में प्राप्त करने के पश्चात ही स्वीकृति निविदा का कार्यादेश दिया जायेगा।
13. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार निम्नहस्ताक्षर कर्ता को रहेगा। RPWA 100 की समस्त शर्तें उस सीमा तक मान्य/लागु होगी जिस सीमा तक के राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के विरोध में नहीं हो।
14. वित्त विभाग के आदेश संख्या एफ-(1)एफ.डी./जी.एफ. एण्ड ए.आर./2007 दिनांक 30.09.11 (सर्कुलर नं. 19/2011) के अनुसार 50.00 लाख रुपये तक की राशि के कार्यों के लिए 500/- व 50.00 लाख रुपये से अधिक राशि के कार्यों के लिए 1000/- रुपये की राशि निविदा शुल्क के अतिरिक्त देनी होगी जो डिमाण्ड ड्राफ्ट या बैंकर चैक के रूप में देय होगी। यह डिमाण्ड ड्राफ्ट या बैंकर चैक मैनेजिंग डायरेक्ट, आर.आई. एस.एल. के पक्ष में व जयपुर में भुगतान योग्य होना चाहिए।
15. नेगोशिएशन की आवश्यकता होने पर ई-मेल व पत्र द्वारा डाक से सूचित किया जायेगा।
16. ई-टेण्डरिंग के लिए निविदादाता हेतु निर्देश :-

- इन निविदाओं में दिलचस्पी लेने वाले निविदा दाता निविदा प्रपत्रों का इन्टरनेट साईट <http://www.eproc.rajabasthan.gov.in> से देख/डाउनलोड कर सकते हैं।
- निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://www.eproc.rajabasthan.gov.in> पर रजिस्टर करवाना होगा। ऑन लाईन निविदा में भाग

- लेने के लिए डिजिटल सर्टिफिकेट है इनफोरमेशन टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी.सी.ए. द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल लेने की आवश्यकता नहीं है।
- निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्मेट में उपरोक्त वेबसाइट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव अकेले भौतिक फॉर्म में स्वीकार्य नहीं होगा।
 - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे की निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्कैन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
 - कोई भी टेण्डर इलेक्ट्रॉनिकली जमा कराने से किसी कारण से लेट हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
 - टेण्डर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑन लाईन दर्ज करे।
17. निविदायें राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के अन्तर्गत आमंत्रित की जाती है। उपर अंकित समस्त प्रावधान/बंधन उस सीमा तक ही लागु होंगे जिस सीमा तक दे उस बिन्दु में उल्लेखित अधिनियम एवं नियमों के विरुद्ध नहीं हो।
18. संवेदक द्वारा प्रस्तुत की गयी दरें एक वर्ष तक मान्य होगी।
19. दर स्वीकृति उपरान्त संवेदक को वर्ष पर्यन्त अलग-अलग कार्य स्थल की उपलब्धता के अनुसार कार्यादेश जारी किया जायेगा।
20. राजकीय अवकाश की स्थिति में अगले कार्य दिवस की तिथी मानी जायेगी।
21. आयुक्त नगर निगम जोधपुर के आदेश क्रमांक 9836 दिनांक 07.02.2020 एवं 9975 दिनांक 14.07.2020 के अनुसार पंजीयन रिव्यू आदेश के तहत निविदा स्वीकार/अस्वीकार की जायेगी।
22. श्रीमान् निदेशक, स्वायत्त शासन विभाग राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.2021 की पालना में वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर.टी.पी.पी. नियम 2013 में Additional Performance Security के लिए नियम 75 -ए के अनुसार Additional Performance Security जमा करवानी होगी।


(अरुण कुमार पुरोहित)
R.A.S.
आयुक्त
जोधपुर नगर निगम दक्षिण

जोधपुर नगर निगम, जोधपुर-दक्षिण

क्रमांक:- / विकास / तृतीय / दक्षिण / 2022-23 / 217

दिनांक:- 27/6/2022

:: ई-निविदा सूचना ::

(यू.बी. संख्या.....)

नगर निगम दक्षिण जोधपुर की ओर से विकास कार्यों हेतु ऑनलाईन निविदा आमंत्रित की जाती है, कार्यों की विस्तृत जानकारी एवं शर्तों इत्यादि वेबसाईट <http://eproc.rajasthan.gov.in>, www.sppp.raj.nic.in पर व जोधपुर नगर निगम दक्षिण की वेबसाईट urban.rajasthan.gov.in /MCJS देखी जा सकती है।

(अरुण कुमार पुरोहित)
R.A.S.

आयुक्त
जोधपुर नगर निगम-दक्षिण

क्रमांक:- 218 to 225

दिनांक:- 27/6/2022

प्रतिलिपि :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. श्रीमान जिला कलेक्टर महोदय, जोधपुर।
2. निदेशक/अधीक्षण अभियन्ता, स्थानीय निकाय विभाग, जयपुर।
3. अधीक्षण अभियन्ता/अधिशाषी अभियन्ता, सा.नि.वि./जोधपुर विकास प्राधिकरण जोधपुर।
4. वरिष्ठ लेखाधिकारी, जोधपुर नगर निगम दक्षिण।
5. राजस्थान संवाद, जयपुर को भेजकर लेख है कि निविदा सूचना एक राज्य स्तरीय एवं एक क्षेत्रीय स्तरीय समाचार पत्र में प्रकाशन हेतु भिजवाये एवं समाचार पत्र के नाम बाबत ईन्टीमेशन मेल नगर निगम जोधपुर दक्षिण को भिजवाये।
6. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि ई-निविदा सूचना urban.rajasthan.gov.in/mcjs एवं sppp.rajasthan.gov.in, पर अपलोड करें एवं निविदा सूचना प्रकाशन हेतु राजस्थान संवाद जयपुर को मेल के माध्यम से भिजवायें।
7. कनिष्ठ अभियन्ता सु श्री अंजली राठौड़ को भेजकर लेख है कि कार्यों की जी-सारणी एवं ई-निविदा सूचना <http://eproc.rajasthan.gov.in> पर अपलोड करे।
8. सूचना पट्ट जोधपुर नगर निगम दक्षिण।

आयुक्त
जोधपुर नगर निगम -दक्षिण

JODHPUR NAGAR NIGAM, SOUTH

G-SCHEDULE

NIT No.

Date

Sr No.

Last Date of Sale :-

Earnest Money : Rs.

Date of Receipt :-

CR No. Dated.

Copy issued to M/s

Name of Work - development work at modern toilet ganeshpura

S.No.	Item	Qty	Unit	Rate	Ammount
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In hard rock (Blasting prohibited) Depth upto 1.5 m	15.60	cum	269.00	4196.40
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	27.07	cum	4340.00	117475.12
3	Random rubble masonry with hard stone in foundation and plinth :Cement mortar 1:6 (1 cement : 6 coarse sand)	16.03	Cum	4245.00	68055.84
4	Extra for random rubble masonry with hard stone in superstructure above plinth level and upto two stories , wall	1.08	Cum.	5134.00	5544.72
5	Extra for coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto two stories.	1.08	Cum.	889.00	960.12
6	Extra for random rubble masonry with hard stone in Square or rectangular pillars	1.08	Cum.	660.00	712.80
7	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand)	28.80	Sqm	264.00	7603.20
8	Finishing walls with water proofing cement paint of required shade :New work (Two or more coats applied @ 3.84 kg/10 sqm).	28.80	Sqm	85.40	2459.52
9	Supplying and fixing Soorsagar Bhura or Equivalent ashlar sills, lintels and dassa, bearing, bed & top surface made perfenctly even, jambs, skirting steps etc. rough dressed: Above 15 cm. and upto 20 cm. thick	2.00	Cum	4475.00	8950.00
10	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	500	Kg	117.50	58750.00
11	Earth filling with available surplus soil excavated from foundations and taken only from outside of building plinth in layers not exceeding 20cm in depth, consolidating each deposited layer including ramming and watering and consolidation with lead up to 50 m and lift upto 1.5 m.	19.20	Cum.	144.00	2764.80

12	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and panelling to be paid for separately) :For fixed portion.Anodised aluminium (anodised transparent or dyed to	200.00	Kg	406.00	81200.00
13	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of PVC / neoprene gasket required (Fittings shall be paid for separately).Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	300.00	Kg	438.00	131400.00
14	Providing and fixing 12mm thick Pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge.Pre laminated particle board with decorative lamination on both sides	20.00	Sqm	1083.00	21660.00
15	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-incharge . (Cost of aluminium snap beading shall be paid in basic item) :With float glass panes of 4.0 mm thickness	18.00	Sqm	986.00	17748.00
16	Providing and fixing double action hydraulic floor spring of approved brand and manufacture IS : 6315 marked, for doors including cost of cutting floors as required, embedding in floors and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge.With stainless steel cover plate	6.00	Each	1883.00	11298.00
17	Providing and fixing expanded grill made of aluminum as per design and drawing having members section of size 7.5mm x 6.0mm and opening of size 102mm x 99mm to aluminum window/vent with required screws, Y and H aluminium sec (as per drawing) at the ends and middle joints respectively complete in all respect as per direction of engineer in charge.Anodised aluminum (anodised transparent 81 dyed to required shade according to IS : 1868. (Minimum anodic coating of grade AC 15, Anodizing to be got done from approved Anodizer)	15.00	Sqm	1945.00	29175.00
18	Providing and fixing expanded grill made of aluminum as per design and drawing having members section of size 7.5mm x 6.0mm and opening of size 102mm x 99mm to aluminum window/vent with required screws, Y and H aluminium sec (as per drawing) at the ends and middle joints respectively complete in all respect as per direction of engineer in charge.Anodised aluminum (anodised transparent 81 dyed to required shade according to IS : 1868. (Minimum anodic coating of grade AC 15, Anodizing to be got done from approved Anodizer)	16.00	Sqm	1946.00	31136.00

19	Supply & fixing of stainless steel pipe railing for ramp railing height, 90 cm. with 40 mm dia stainless steel pipe with 18 gauge with drop (vertical post) at 90 cm. C/C and intermediate horizontal pipe with suitable height of same size and gauge with coupling, grinding and polishing & fix of master pieces as per required point as per approved design of Engineer incharge.Total	60	mtr	2493	149580.00
20	Kota stone slabs 25 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	16	Sqm	1538	24608.00
21	Providing and fixing of precast concrete interlocking tiles of desired shape of M 30 grade manufactured from fully computerized automatic stationery hydraulic vibro pressed machine and fully computerized automatic batching plant of class A1/A2 as per BS 6717:2001. The CC interlocking paving blocks be laid on average 50mm. thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer in charge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications. Tensile splitting strength, abrasion and braking load etc. as per BS 6717:2001, Grey cement.80mm thick	200	Sqm	664	132800.00
22	Providing and fixing precast cement concrete M-20 grade (Using mechanical Concrete Mixer) kerb stone top and bottom width 115 and 165 mm respectively, 250 mm high on 150 mm thick PCC M-10 grade foundation as per design, including fixing at site as per clause 408 of MoRT&H Specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	60	metre	312.5	18750.00
23	Stone tile work for wall lining upto 10 m height with special adhesive over 12mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) including pointing in white cement with an admixture of pigment to match the stone shade.Raj Nagar plain white marble/ Udaipur green marble/ Zebra black marble.	170	Sqm	2000	340000.00
24	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).Dark shade using ordinary cement.	20	sqm	854	17080.00
25	Supplying and stacking good earth at site of work. Note: 1) Loading, unloading and carriage to be paid extra as per actual lead. 2) Earth measured in stacks will be reduced by 20% for payment	45	CUM	299.5	13477.50

26	Supply at site of work well decayed farm yard manure, from any available source, approved by the engineer in charge including screening and stacking.	7.5	CUM	671	5032.50
27	Grassing with 'Doobs' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for moving including supplying good earth if needed. In rows 15 cm apart in either direction	150	SQM	34.5	5175.00
28	Maintenance of Lawns with Fine Grassing for the First Year	150	SQM	170	25500.00
29	Planting permanent hedges including digging of trenches, 60 cm wide and 45 cm deep, refilling the excavated earth mixed with farmyard manure, supplied at the rate of 4.65 cum per 100 metres and supplying and planting hedge plants at 30 cm apart.	60	METRE	348	20880.00
30	Maintenance of Hedge for one year	60	METRE	290.5	17430.00
					1371402.52

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
4. कार्य स्थल पर कार्य संबंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
9. सशर्त निविदा स्वीकार नहीं होगी।



EXECUTIVE ENGINEER
NAGAR NIGAM SOUTH JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

OFFICE OF THE NAGAR NIGAM, JODHPUR

G-SCHEDULE

NIT No. Date

Sr No.

Last Date of Sale :-

Earnest Money : Rs.

Date of Receipt :-

CR No. Dated.

Copy issued to M/s

Name of work:- Development work at park situated in Balaji nagar in ward no 80 of Nagar Nigam South, Jodhpur

S.No.	Item	Qty.	Unit	Rate in Rs.	Amount
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m	229.95	cum	164.00	37711.8
2	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil	63.00	cum	145.00	9135
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	34.75	cum	3360.00	116743.2
4	Random rubble masonry with hard stone in foundation and plinth : 25.1.1 Cement mortar 1:6 (1 cement : 6 coarse sand)	132.58	CUM	3190.00	422930.2
5	Extra for random rubble masonry with hard stone in superstructure above plinth level and upto two stories.	79.80	cum	3812.00	304197.6
6	Extra for random rubble masonry with hard stone in : Square or rectangular pillars	15.00	cum	449.00	6735
7	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded 20mm nominal size stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 75mm thick	97.80	sqm	548.00	53594.4
8	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Raised and cut pointing	420.00	sqm	260.00	109200
9	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	22.68	sqm	210.00	4762.8
10	Providing sand stone slab for roofing and laying them in cement mortar 1 : 4 (1 cement : 4 coarse sand) over wooden karries or R.C.C. battens (Karries and battens to be paid separately) including pointing the ceiling joints with cement mortar 1:3 (1 cement : 3 fine sand) complete :	17.40	sqm	546.00	9500.4
11	Finishing walls with water proofing cement paint of required shadeew work (Two or more coats applied @ 3.84 kg/10 sqm).	420.00	sqm	55.50	23310


12	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1200.00	kg	87.50	105000
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	100.00	sqm	69.00	6900
14	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm. The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer in charge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications.	210.00	sqm	641.00	134610
15	Providing and fixing precast cement concrete M-20 grade (Using mechanical Concrete Mixer) kerb stone top and bottom width 115 and 165 mm respectively, 250 mm high on 150 mm thick PCC M-10 grade foundation as per design, including fixing at site as per clause 408 of MoRT&H Specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	280.00	metre	254.00	71120
16	Supplying, erecting and fixing in position specified precast RCC bench made of RCC grade M-30 consisting of 2 Nos. "L" shaped base support of thickness 100 mm back height 1000mm, front height 450 mm, base width 420mm and 5 Nos. RCC planks of size of 1500x100 x 50 mm and 1 Nos RCC planks of 150x200x50mm including joining all parts with galvanised nuts and bolts of suitable size. All bolts to be sealed after assembly with nice finish and appearance and level complete in all respect as per direction of engineer in charge. Every bench should have a manufacture's logo of appropriate size Engraved at suitable place.	4.00	nos	7600.00	30400
17	Providing and fixing angle iron frame 25 x 25 x 3mm for ventilators fixed with 24 gauge square mesh of 14 gauge stainless steel wire including 10 mm square bars at interval of 100 mm welded to frame with metal beading of 20 x 3mm complete in all respect as per technical specifications and drawings as per technical specification and as per direction of Engineer.	0.41	sqm	92.50	37.925
18	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.	3.24	sqm	2680.00	8683.2
19	Providing and fixing T-iron frames for doors, windows and ventilators of mild steel Tee-sections, joints mitred and welded with 15x3 mm lugs 10cm long embedded in cement concrete blocks 15x10x10 cm of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or with dash fastener or rawl plugs and screws or with fixing clips or with bolts and nuts as require including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.	100.00	kg	71.00	7100

20	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including priming coat with cement primer.	72.00	sqm	86.00	6192
21	Providing, lowering, laying in trenches, aligning, fixing in position and jointing socketed rubber gasket type ISI marked uPVC pipes of Class III (6 Kg/sqcm) suitable for potable water with rubber ring joints (as per IS 4985-2000) of following outer dia with all accessories (excluding specials) complete including all material, labour, hydraulic testing and commissioning as per Technical Specifications and as per direction of Engineer. Note : E/w to be measured and paid separately. 110 mm dia	20.00	metre	273.00	5460
	160 mm dia	10.00	metre	564.00	5640
22	Brick work with modular bricks of class designation 75 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand).	1.35	cum	3640.00	4914
23	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Vitreous china Orissa pattern W.C. pan of size 580x440mm with integral type foot rests.	2.00	each	3570.00	7140
24	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350mm and 340x410x265mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern.	2.00	each	3510.00	7020
25	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require : White Vitreous China Angle back wash basin size 400x400 mm with single 15 mm C.P. brass pillar tap.	2.00	each	3510.00	7020
26	Kota stone slab flooring 25mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : Area of each slab 900 to 2000 sqcm	7.50	sqm	1020.00	7650
27	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall				
a	a) 15 mm nominal outer dia .Pipes.	30.00	Mtr	171.00	5130
b	b) 25 mm nominal outer dia .Pipes.	30.00	Mtr	288.00	8640
28	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	1.00	Nos	402.00	402
29	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	1.00	Nos	497.00	497
30	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Ltr	6.50	6500

31	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm nominal bore.	5.00	Nos	377.00	1885
32	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. 15 mm nominal bore.	5.00	Nos	342.00	1710
33	Constructing brick masonry road gully chamber 50x45x60 cm with bricks of class designation 75 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm precast R.C.C. horizontal grating with frame complete as per standard design : With bricks	1.00	Nos	3510.00	3510
34	Providing and fixing unplasticized Poly Vinyl Chloride (UPVC) SWR pipes type 'B' for sciland waste discharge system (IS : 13592: 1992 marked) of approved quality/ make. Nahni Trap with Jali 4"	2.00	Nos	176.00	352
35	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 15 mm nominal bore	2.00	Nos	280.00	560
36	Earth filling with available surplus soil excavated from foundations and taken only from outside of building plinth in layers not exceeding 20cm in depth, consolidating each deposited layer including ramming and watering and consolidation with lead up to 50 m and lift upto 1.5 m.	36.00	cum	98.00	3528
37	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth 5 km	328.95	CUM	165	54276.75
Total					1599698.28

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
4. कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
9. सशर्त निविदा स्वीकार नहीं होगी।


EXECUTIVE ENGINEER
NAGAR NIGAM SOUTH JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)