

#### जोधपुर नगर निगम, (दक्षिण)



पोलोटेक्निक कॉलेज परिसर, रेजीडेन्सी रोड़, जोघपुर E-Mail-nnjelectrical@gmail.com

क्रमांक :- रो./कार्य/2022/11194

दिनांक :- 18/10/2022

#### अल्पकालिन निविदा सूचना

	Contract Charles		
IID	No		
U.B.	NO		

नगर निगम जोधपुर की ओर से निम्नलिखित निविदा सूचना क्रय/कार्य करने हेतु सीलबन्द निविदाए आमंत्रित की जाती है। जो इच्छुक संवेदक निविदा में हिस्सा लेना चाहते हैं वे अपनी सीलबन्द निविदाये निम्न हस्ताक्षकर्ता के समक्ष प्रत्येक मद के आगे अंकित तिथि को प्रातः 11:00 बजे तक प्रेषित कर सकते है। निविदायें सम्बंधी प्रपत्र इसी दिनांक को दोपहर 2:00 बजे उपस्थित निविदाताओं या उनके प्रतिनिधियों के समक्ष खोली जावेगी।

विस्तृत विवरण व शर्तों के लिए नगर निगम कार्यालय से जानकारी प्राप्त की जा सकती है।

क्र.स.	कार्य का नाम	अनु.लागत लाखो में	निविदा बेचने की तिथि	निविदा प्राप्ति की तिथि
01	वार्ड संख्या 13 में एलईडी लाईट लगाने का कार्य।	99912.00	21.10.2022	21.10.2022
02	वार्ड संख्या 10 में एलईडी लाईट लगाने का कार्य।	99982.50	21.10.2022	21.10.2022
03	झालामण्ड स्थित मोटर गैरेज में वाटर कुलर मशीन लगाने का कार्य।	91769.00	21.10.2022	21.10.2022

अधिशाषी अभियन्ता (विद्युत) नगर निगम (दक्षिण)जोधपुर दिनांक :- 18/10/2027

क्रमांक :- रो. / कार्य / 2022 / | 2 | 35 to | 2 | 98 प्रतिलिपि :-

- 01. स्टोर किपर / स्टेशनर लिपिक, नगर निगम (दक्षिण) जोधपुर।
- 02. बिल लिपिक, नगर निगम (दक्षिण) जोधपुर।
- 03. ओसवाल डाटा प्रोसेस, नगर निगम, जोधपुर।
- 04. नोटिस बोर्ड, नगर निगम (दक्षिण) जोधपुर।

५ अधिशाषी अभियन्ता (विद्युत) नगर निगम (दक्षिण)जोधपुर

# Nagar Nigam (South), Jodhpur Supply and Fixing of Led Light at Nagar Nigam South Jodhpur (ward 13)

Name of work:-

RUIDP SOR 2022

Schedule

Part A ("G" Schedule)

S.n.	CODEno	PARTICULARS	QT	Y.	RAT	E	AMOUNT
-	E181300	Providing & Fixing of IK07 IP 66 protected LED Street Light Luminaire on existing bracket/pole. Fixture made of powder coated single piece pressure die cast aluminum LM6/ ADC12 material with heat dissipation fins on housing with UV stabilized PC/Toughened Glass cover (UV stablzation report submitted for UV cover) and secondary lens on each LED & should be SMD type. The System level Luminaire efficacy >=120 lm/ wt with High Power LEDs is to be used and potted driver must be potted & has a unique BIS R number with Input Voltage AC 120 to 270 V AC with High voltage Cutoff @>=300 V AC and Auto resetting Safety ,Input Frequency 50Hz±3% Power Factor >0.95 driver Efficiency >85% ,THD(I) <10% Humidity 10% to 90% RH Working Temp -5C to 45C. driver current <1000mA shown in LM79 report. The luminaire shall be BIS certified and T.C. certified. Life Expectancy Equal or more than 50000 burning hrs with Minimum 70% lumen maintened ,color Rendering Index >70 and CCT 5700K +355K. Surge protection shall be min ≥ 4 KV internal and min 10 KV external, driver should be Phase to phase protection of 440 V for 4 Hrs. Manufactures Word Mark/Name Engraved/Embossing on die cast housing to allow traceability/authenticity. Fixture shall be AS PER IS 10322 Complianced. OEM Must have its own in					
	E181305	house NABL lab setup for all testing facilities for LED fixtures (LM79/LM80)  LED street light fixture 70 Watt	18	Nos	5250.00	Each	94500.00
2	E181700	Providing & Fixing of Street light bracket made out from following size of 'B' class, Medium class G.I. Pipe confirming to IS: 1239 P-1 (2004) with heavy duty pole clamp, Saddles suitable fastners etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR	10	Nas	279.00	Each	5022.00
	E181703	32 mm Dia.	18	Nos	279.00	Eacn	3022.00
3	E040500	Supply & drawing Wiring for sub mains as per PWD specification for electrical Works with ISI marked (IS:694), 1100 Volts grade PVC insulated flat twin core sheathed solid aluminium conductor with 10 SWG G.I. Support wire duly clipped including all as per pre approved by Engineer in charge, making connections, as required. OEM Must have its own in house NABL lab setup for all testing facilities for wires. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR.			30.00	PM	300.00
	E040501	4.0 sq.mm	10	Mtr	39.00	RM	390.00
_	2010201	Total (G-Schedule)					99912.00



I/We agree to do the above "G" Schedule	above/Below with RUIDP 2022 and JMC terms and	conditions
---	---	------------

Signature of Contractor

## Nagar Nigam (South), Jodhpur Supply and installation of Water Cooler with purifier at Nigam Store (BRTS Bus Stand)

Name of work:-

RUIDP SOR 2022

schedule

Part A ("G" Schedule)

S.n.	CODEno	PARTICULARS	Q'	TY.	RAT	E	<b>AMOUNT</b>
1	E223600	Supply, Installation, Testing and Comissioning of ISO certified company made self contained drinking water coolar with BEE Rated energy efficient hermetic sealed type compressor, non CFC refrigerent suitable for operation on 230V/1pH/50Hz ac supply, Full stainless steel (S304)body and tank, stainless steel water tray, minimum two nos faucets and suitable drainage system complete in all respect with 300mm height MS fabricated and painted plateform. complete in all respect of the following capacity. NABL accredeated / CPRI/ ERDA lab testing reports with OEM certificate must submitted to engineer in charge. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR.					
	E223602	Cooling capacity 150 Ltr./Hr. and storage capacity 150 Ltrs	1	Nos	56770.0	Each	56770.00
1.19		Total (G-Schedule)					56770.00

	Schedule			("H" Schedule)					
S.n.	CODEno	PARTICULARS	Q	TY.	RA	ΓE	AMOUNT		
ı		Supply, Installation, Testing and Comissioning of ISO certified company made 50 LPH RO, UV water purifier system 100 liter per hour Stainless Steel fully Automatic with auto shut off sensor, TDS adjuster, Filter0.1 micron, carbon 0.1 micron RO membrane 0.1Ultra Violet filter, remove upto 99% of contaminants including arsenic, chlorine, lead, fluoride, heavy metals, bacteria, virus and 1000+ contaminants, high quality quick connect fitting in all respect as per direction of engineering incharge.	1	Nos		Each			

XEN(Elect.) **JMC** 

I/We agree to do the above "G" Schedule	above/Below	with RUIDP 2022 and JMC terms and conditions.
H Schedule Item	Each	

Signature of Contractor

### Nagar Nigam (South), Jodhpur Supply and Fixing of Led Light at Nagar Nigam South Jodhpur (ward 10)

Name of work:-

RUIDP SOR 2022

Schedule

Part A ("G" Schedule)

S.n.	CODEno	PARTICULARS	QT	Y.	RAT	E	AMOUNT
1	E181300	Providing & Fixing of IK07 IP 66 protected LED Street Light Luminaire on existing bracket/pole. Fixture made of powder coated single piece pressure die cast aluminum LM6/ ADC12 material with heat dissipation fins on housing with UV stabilized PC/Toughened Glass cover (UV stablzation report submitted for UV cover) and secondary lens on each LED & should be SMD type. The System level Luminaire efficacy >= 120 lm/ wt with High Power LEDs is to be used and potted driver must be potted & has a unique BIS R number with Input Voltage AC 120 to 270 V AC with High voltage Cutoff @>=300 V AC and Auto resetting Safety ,Input Frequency 50Hz±3% Power Factor >0.95 driver Efficiency >85%, THD(I) <10% Humidity 10% to 90% RH Working Temp -5C to 45C. driver current <1000mA shown in LM79 report. The luminaire shall be BIS certified and T.C. certified. Life Expectancy Equal or more than 50000 burning hrs with Minimum 70% lumen maintened ,color Rendering Index >70 and CCT 5700K +355K. Surge protection shall be min ≥ 4 KV internal and min 10 KV external. driver should be Phase to phase protection of 440 V for 4 Hrs. Manufactures Word Mark/Name Engraved/Embossing on die cast housing to allow traceability/authenticity. Fixture shall be AS PER IS 10322 Complianced. OEM Must have its own in bouse NABI. Tab setup for all testing facilities for LED fixtures. (LM79/LM80)					
	E181303	LED street light fixture 45 Watt	21	Nos	4405.00	Each	92505.00
2	E1817#0	Providing & Fixing of Street light bracket made out from following size of 'B' class, Medium class G.I. Pipe confirming to IS: 1239 P-1 (2004) with heavy duty pole clamp, Saddles suitable fastners etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/work, refer Annexure "A" attached with this BSR					
1	E181703	32 mm Dia.	21	Nos	279.00	Each	5859.00
3		Supply & drawing Wiring for sub mains as per PWD specification for electrical Works with ISI marked (IS:694), 1100 Volts grade PVC insulated flat twin core sheathed solid aluminium conductor with 10 SWG G.I. Support wire duly clipped including all as per pre approved by Engineer in charge, making connections, as required. OEM Must have its own in house NABL lab setup for all testing facilities for wires. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR.					
7	-	4.0 sq.mm	41.5	Mtr	39.00	RM	1618.50
		Total (G-Schedule)					99982.50
		Say Rs.					1.00 Lac



I/We agree to do the above "G" Schedule ......above/Below with RUIDP 2022 and JMC terms and conditions.

Signature of Contractor