

कार्यालय नगरपालिका मण्डल मुकुन्दगढ (झुन्डुनु) राज.

क्रमांक : नपासु/2018-19/ 2073

दिनांक :- 13.09.2019

-: निविदा सूचना 05/2019-20:-

नगरपालिका मुकुन्दगढ द्वारा विभिन्न प्रकार संकर्मों के लिए राजकीय विभागों में पंजीकृत संक्षम श्रेणी के संवेदकों से मोहरबन्द निविदाएं आमंत्रित की जाती है। जो कार्य के सम्मुख अंकित निविदा शुल्क जमा करवा कर दिनांक 24.09.2019 समय दोपहर 02.00 बजे तक प्राप्त की जाकर दिनांक 25.09.2019 को दोपहर 02.00 बजे तक अधोहस्ताक्षरकर्ता के कक्ष में जमा करवाई जा सकती हैं। प्राप्त निविदाओं को दिनांक 25.09.2019 को दोपहर 03.00 बजे उपस्थित संवेदकों/उनके प्रतिनिधि के समक्ष खोली जावेगी। निविदाये <http://urban.rajasthan.gov.in/ulbmukundgarh> पर भी देखी जा सकती है।

क्र.सं.	कार्य का विवरण	अनुमानित राशि लाखों में	अमानता राशि	निविदा शुल्क	कार्य अवधि
1	वार्ड नं. 01 राजू कटारिया के घर से महेश सैनी के घर तक सी.सी. सड़क निर्माण कार्य	0.99	1980	500	1 माह
2	वार्ड नं. 18 मुकुन्दगढ बस स्टैण्ड पर सी.सी. सड़क निर्माण कार्य	0.97	1940	500	1 माह
3	वार्ड नं. 20 रामदेवी जी मंदिर में सार्वजनिक चौक में सी.सी. सड़क निर्माण कार्य	0.75	1500	500	1 माह
4	वार्ड नं. 11 से 20 में विभिन्न स्थानों पर सी.सी. पेव मरम्मत कार्य	0.93	1860	500	1 माह
5	वार्ड नं. 01 से 10 में विभिन्न स्थानों पर सी.सी. पेव मरम्मत कार्य	0.99	1980	500	1 माह
6	वार्ड नं. 03 गनेड़ी बालाजी बगीची से बनवारी सैनी के घर तक सी.सी. सड़क निर्माण कार्य	0.98	1960	500	1 माह
7	वार्ड नं. 20 में बदरू काजी के घर से हरिराम के घर तक सी.सी. सड़क निर्माण कार्य	0.98	1960	500	1 माह
8	वार्ड नं. 07 में महिपाल डोटसरा के घर से मनोज शर्मा के घर तक सी.सी. सड़क निर्माण कार्य	0.98	1960	500	1 माह
9	वार्ड नं. 18 में भवरलाल लाईनमेन के घर से खेत तक सी.सी. सड़क निर्माण कार्य	0.99	1980	500	1 माह
10	वार्ड नं. 07 में रतन चौधरी के घर से शंकर जांगिड़ के घर तक सी.सी. सड़क निर्माण कार्य	0.93	1860	500	1 माह
11	वार्ड नं. 03 में बनवारी सैनी के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य	0.94	1880	500	1 माह
12	वार्ड नं. 01 में राजू सैनी के घर से मैन मण्डावा रोड़ तक सी.सी. सड़क निर्माण कार्य	0.98	1960	500	1 माह
13	वार्ड नं. 16 में सुल्तान के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य	0.67	1340	500	1 माह
14	वार्ड नं. 16 में चेताराम के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य	0.65	1300	500	1 माह
15	वार्ड नं. 20 में याकूब काजी के घर से गुलाब काजी के घर तक सी.सी. सड़क निर्माण कार्य	0.99	1980	500	1 माह
16	वार्ड नं. 20 पोरवाल गेस्ट हाउस से बिसातीयों के घर तक सी.सी. सड़क निर्माण कार्य	0.99	1980	500	1 माह
17	वार्ड नं. 18 में अन्तर तेली के घर से इकबाल के घर तक सी.सी. सड़क निर्माण कार्य	0.84	1680	500	1 माह
18	वार्ड नं. 08 में मोटेन स्कूल से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य	0.49	980	500	1 माह
19	वार्ड नं. 08 में अमर सिंह के घर से आर.के. स्कूल तक सी.सी. सड़क निर्माण कार्य	0.84	1680	500	1 माह
20	वार्ड नं. 07 में सुरेश सैनी के घर से मुरारी शर्मा के घर तक सी.सी. सड़क निर्माण कार्य	0.81	1620	500	1 माह
21	वार्ड नं. 14 में संजु जांगिड़ के घर से नागर जांगिड़ के घर तक सी.सी. सड़क निर्माण कार्य	1.00	2000	500	1 माह
22	वार्ड नं. 16 में नत्थूसिंह के घर से चेताराम के घर तक सी.सी. सड़क निर्माण कार्य	0.98	1960	500	1 माह
23	वार्ड नं. 16 में कजोड़ के घर से सुल्तान के घर तक सी.सी. सड़क निर्माण कार्य	0.99	1980	500	1 माह
कुल योग		20.66	41320	11500	

शर्तें :-

- संशर्त निविदा स्वीकार नहीं होगी।
- निविदा शुल्क एवं अमानता जमा करवाये जाने के उपरान्त ही निविदा प्रपत्र दिया जावेगा।
- पंजीयन प्रमाण पत्र/जी.एस.टी./पैन कार्ड की प्रति संलग्न करने पर ही निविदा प्रपत्र दिया जावेगा।
- संवेदक को श्रम अधिनियम एवं संनिर्माण कर्मकार अधिनियम एवं उपकर अधिनियम 1996 व इससे संबंधित सभी नियमों की पालना करनी होगी।
- आरटीटीपी एक्ट 2012 नियम 2013 की पालना करनी होगी।
- निविदा प्राप्त तिथि को अवकाश होने पर आगामी कार्य दिवस माना जावेगा।
- बीएसआर/एसओआर से दर कम आने पर अन्तर राशि जमा करवानी होगी
- जी शिड्यूल मे दी गई मात्रा घटाई/बढ़ाई जा सकती है।
- सक्षम कमेटी के पास निविदा स्वीकार/अस्वीकार करने का अधिकार सुरक्षित है।

अधिसाक्षी अधिकारी
नगर पालिका मुकुन्दगढ

क्रमांक : नपासु/2018-19/

दिनांक :-

प्रतिलिपि सूचनार्थ एवं आवश्यक कार्यवाही हेतु:-

- संवाददाता सीमा संदेश को भेजकर लेख है कि उक्त निविदा न्यूनतम स्थान पर स्वीकृत दर पर प्रकाशित कर बिल कार्यालय को भिजवायें।
- कनिष्ठ अभियंता नगर पालिका मुकुन्दगढ
- लेखा शाखा नगर पालिका मुकुन्दगढ
- सुरक्षित पत्रावली

अधिसाक्षी अधिकारी
नगर पालिका मुकुन्दगढ

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 01 राजू कटारिया के घर से महेश सैनी के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.99
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	2000
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed within specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work: वार्ड नं. 01 में राज कटारिया के घर से महेश सैनी के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	30.00	4.00	0.50	60.00	Cum	164.00	9840.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	30.00	4.00	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	30.00	4.00	0.10	12.00	Cum	4700.00	56400.00
							Total Amount Rs.		98760.00

Say Rs. 0.99Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.99 Lacs तकनीकी

स्वीकृति प्रदान की जाती है। TSN-30

40/12/20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 18 मुकुन्दगढ बस स्टेण्ड पर सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.97
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1940
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)


Detailed Estimate

Name of Work : वार्ड नं. 18 में मुकुन्दगढ़ बस स्टेण्ड पर सी.सी. सड़क मरम्मत कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	95	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-30							
		1	16.00	6.00	0.20	19.20	Cum	5060.00	97152.00
								Total Amount Rs.	97152.00

Say Rs. 0.97 Lacs


Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.97 Lacs की तकनीकी

स्वीकृति प्रदान की जाती है। TS No 31

2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 20 रामदेवी जी मंदिर में सार्वजनिक चौक में सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.75
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1500
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 10 में रामदेव जी मंदिर में सार्वजनिक चौक में सी.सी. सड़क मरम्मत कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	2.4	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Cement Concrete Grade M-15 and above and PCC blocks				13.50	Cum	427.00	5764.50
			15.00	6.00	0.15	13.50	Cum	427.00	5764.50
2	1.1	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth UP To 03 KM				13.50	Cum	137.00	1849.50
3	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion				9.00	Cum	2710.00	24390.00
		1	15.00	6.00	0.10	9.00	Cum	2710.00	24390.00
4	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20				9.00	Cum	4700.00	42300.00
		1	15.00	6.00	0.10	9.00	Cum	4700.00	42300.00
								Total Amount Rs.	74304.00

Say Rs. 0.75 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.75 लाख तकनीकी
स्वीकृति प्रदान की जाती है।

T.S.N. 32

20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 11 से 20 में विभिन्न स्थानों पर सी.सी. पेच मरम्मत कार्य
Amount of "G" schedule	0.93
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1860
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed within specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound to follow all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email, ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)									
Detailed Estimate									
Name of Work :		वार्ड नं. 11 से 20 में विभिन्न स्थानों पर सी.सी. पेच मरम्मत कार्य							
BASED ON BSR RUIDP SOR 2017									
S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos	L	B	H				
1	2.4	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Cement Concrete Grade M-15 and above and PCC blocks				16.88	Cum	427.00	7205.63
			45.00	2.50	0.15	16.88	Cum	427.00	7205.63
2	1.1	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth UP To 03 KM				16.88	Cum	137.00	2311.88
						16.88	Cum	137.00	2311.88
3	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion				11.25	Cum	2710.00	30487.50
		1	45.00	2.50	0.10	11.25	Cum	2710.00	30487.50
4	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20				11.25	Cum	4700.00	52875.00
		1	45.00	2.50	0.10	11.25	Cum	4700.00	52875.00
								Total Amount Rs.	92880.00
Sav Rs. 0.93 Lacs									

Say Rs. 0.93 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.93 Lacs की तकनीकी

स्वीकृति प्रदान की जाती है। 75 N. 34

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO _____

"G" Schedule

NAME OF WORK:-	वार्ड नं. 01 से 10 में विभिन्न स्थानों पर सी.सी. पेव मरम्मत कार्य
Amount of "G" schedule	0.99
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1980
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 01 से 10 में विभिन्न स्थानों पर सी.सी. पेच मरम्मत कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	2.4	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer. Cement Concrete Grade M-15 and above and PCC blocks				18.00	Cum	427.00	7686.00
			48.00	2.50	0.15				
2	1.1	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth UP To 03 KM				18.00	Cum	137.00	2466.00
3	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion				12.00	Cum	2710.00	32520.00
		1	48.00	2.50	0.10				
4	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20				12.00	Cum	4700.00	56400.00
		1	48.00	2.50	0.10				
Total Amount Rs.									99072.00

Say Rs. 0.99 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.99 Lacs की तकनीकी

स्वीकृति प्रदान की जाती है।

TSN. 33

20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 03 गनेड़ी बालाजी बगीची से बनवारी सैनी के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.98
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1960
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 03 में गनेड़ी बालाजी बगीची से बनवारी सैनी के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	30.00	4.00	0.45	54.00	Cum	164.00	8856.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	30.00	4.00	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	30.00	4.00	0.10	12.00	Cum	4700.00	56400.00
							Total Amount Rs.		97776.00

Say Rs. 0.98 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.98 Lacs की तकनीकी
स्वीकृति प्रदान की जाती है।

TSN-35
2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

कार्य - 7

ISSUE TO -----

"G" Schedule	
NAME OF WORK:-	वार्ड नं. 20 में बदरु काजी के घर से हरिराम के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	.. 0.98
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1960
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)									
Detailed Estimate									
Name of Work :		वार्ड नं. 20 में बदरूकाजी के घर से हरिराम के घर तक सी.सी. सड़क निर्माण कार्य							
BASED ON BSR RUIDP SOR 2017									
S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	20.00	6.00	0.45	54.00	Cum	164.00	8856.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	20.00	6.00	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	20.00	6.00	0.10	12.00	Cum	4700.00	56400.00
							Total Amount Rs.		97776.00
Say Rs. 0.98 Lacs									

Say Rs. 0.98 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rsकी तकनीकी

स्वीकृति प्रदान की जाती है।

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 07 में महिपाल डोटासरा के घर से मनोज शर्मा के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.98
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1960
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 07 में महिपाल डोटासरा के घर से मनोज शर्मा के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	30.00	4.00	0.45	54.00	Cum	164.00	8856.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	30.00	4.00	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	30.00	4.00	0.10	12.00	Cum	4700.00	56400.00
								Total Amount Rs.	97776.00

Say Rs. 0.98 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rsकी तकनीकी

स्वीकृति प्रदान की जाती है।

TSN-37

2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO

"G" Schedule

NAME OF WORK:-	वार्ड नं. 18 में भंवरलाल लाईनमेन के घर से खेत तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.99
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1980
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 18 में भवरंलाल बिसनिया के घर से खेत तक सी.सी. सड़क निर्माण कार्य
२०१८/१९

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	48.00	2.50	0.50	60.00	Cum	164.00	9840.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	48.00	2.50	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383. maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	48.00	2.50	0.10	12.00	Cum	4700.00	56400.00
								Total Amount Rs.	98760.00

Say Rs. 0.99Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.99Lacs की तकनीकी

स्वीकृति प्रदान की जाती है।

TS No 38

20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule	
NAME OF WORK:-	वार्ड नं. 07 में रतन चौधरी के घर से शंकर जांगिड़ के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.93
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest-Money	1860
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 07 में रतन चौधरी के घर से शंकर जांगीड़ के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	30.00	3.70	0.60	66.60	Cum	164.00	10922.40
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	30.00	3.70	0.10	11.10	Cum	2710.00	30081.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	30.00	3.70	0.10	11.10	Cum	4700.00	52170.00
							Total Amount Rs.		93173.40

Say Rs. 0.93 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.93 Lacs की तकनीकी
स्वीकृति प्रदान की जाती है।

TSN- 39
20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO _____

"G" Schedule

NAME OF WORK:-	वार्ड नं. 03 में बनवारी सैनी के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.94
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1880
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed within specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderer has to be in agreement with the office.
11. The Tenderer will be bound to follow all directions of Engineer-In charge during the execution of work.
12. The Amount of unbalanced bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)									
Detailed Estimate									
Name of Work :		वार्ड नं. 03 में बनवारी सैनी के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य							
BASED ON BSR RUIDP SOR 2017									
S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	28.00	4.00	0.60	67.20	Cum	164.00	11020.80
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	28.00	4.00	0.10	11.20	Cum	2710.00	30352.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	28.00	4.00	0.10	11.20	Cum	4700.00	52640.00
								Total Amount Rs.	94012.80
Say Rs. 0.94 lacs									

Say Rs. 0.94 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.94 की तकनीकी

स्वीकृति प्रदान की जाती है।

TSN-40

20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO -----

"G" Schedule	
NAME OF WORK:-	वार्ड नं. 01 में राजू सैनी के घर से, मैन मण्डावा रोड़ तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.98
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1960
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 01 में राजु सैनी के घर से मेन मंडावा रोड़ तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	30.00	4.00	0.50	60.00	Cum	164.00	9840.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	30.00	4.00	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	30.00	4.00	0.10	12.00	Cum	4700.00	56400.00
								Total Amount Rs.	98760.00

Say Rs. 0.99Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs0.98.....की तकनीकी

स्वीकृति प्रदान की जाती है।

TS No 41

20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 16 में सुल्तान के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.67
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1340
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer

Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 16 में सुल्तान के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	20.00	4.00	0.60	48.00	Cum	164.00	7872.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	20.00	4.00	0.10	8.00	Cum	2710.00	21680.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	20.00	4.00	0.10	8.00	Cum	4700.00	37600.00
								Total Amount Rs.	67152.00

Say Rs. 0.67 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.67 Lacs

स्वीकृति प्रदान की जाती है।

TS No - 42
2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 16 में चेताराम के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.65
Ref. of RUIDP SOR 2017	RUIDP.SOR
BID Cost	500
Earnest Money	1300
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)									
Detailed Estimate									
Name of Work :		वार्ड नं. 16 में चेताराम के घर से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य							
BASED ON BSR RUIDP SOR 2017									
S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	20.00	4.00	0.45	36.00	Cum	164.00	5904.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	20.00	4.00	0.10	8.00	Cum	2710.00	21680.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	20.00	4.00	0.10	8.00	Cum	4700.00	37600.00
							Total Amount Rs.		65184.00

Say Rs. 0.65 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rsकी तकनीकी

स्वीकृति प्रदान की जाती है। TS No - 43

2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

कार्य स.15

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 20 में याकूब काजी के घर से गुलाब काजी के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.99
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1980
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 20 में याकूब काजी के घर से गुलाब काजी के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	25.00	5.00	0.30	37.50	Cum	164.00	6150.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	25.00	5.00	0.10	12.50	Cum	2710.00	33875.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	25.00	5.00	0.10	12.50	Cum	4700.00	58750.00
								Total Amount Rs.	98775.00

Say Rs. 0.99 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rsकी तकनीकी

स्वीकृति प्रदान की जाती है।

T.S No - 44

2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO _____

"G" Schedule

NAME OF WORK:-	वार्ड नं. 20 पोरवाल गेस्ट हाउस से बिसातीयों के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.99
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1980
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	Q1 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed within specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 20 में पोरवाल गेस्ट हाउस से बिसायतीयों के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	50.00	2.50	0.30	37.50	Cum	164.00	6150.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	50.00	2.50	0.10	12.50	Cum	2710.00	33875.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	50.00	2.50	0.10	12.50	Cum	4700.00	58750.00
								Total Amount Rs.	98775.00

Say Rs. 0.99 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.99 Lacs की तकनीकी

स्वीकृति प्रदान की जाती है।

TS-110-45

20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 18 में अन्तर तेली के घर से इकबाल के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.84
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1680
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)									
Detailed Estimate									
Name of Work :		वार्ड नं. 18 में अन्तर तेली के घर से इकबाल के घर तक सी.सी. सड़क निर्माण कार्य							
BASED ON BSR RUIDP SOR 2017									
S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	25.00	4.00	0.60	60.00	Cum	164.00	9840.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength. finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	25.00	4.00	0.10	10.00	Cum	2710.00	27100.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	25.00	4.00	0.10	10.00	Cum	4700.00	47000.00
							Total Amount Rs.		83940.00

Say Rs. 0.84 Lacs

Junior Engineer
Municipal Board N Mukundgarh

T.S.N. 46
2019-20

Rs. 0.84 Lacs तकनीकी
स्वीकृति प्रदान की जाती है।

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 08 में मोन्टेन स्कूल से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.49
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	980
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 8 में मोन्टेन स्कूल से मुख्य सड़क तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	13.00	4.50	0.60	35.10	Cum	164.00	5756.40
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	13.00	4.50	0.10	5.85	Cum	2710.00	15853.50
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	13.00	4.50	0.10	5.85	Cum	4700.00	27495.00
								Total Amount Rs.	49104.90

Say Rs. 0.49 Lacs

Junior Engineer
Municipal Board N Mukundgarh

T.S. No - 47 Rs 0.49 की तकनीकी
स्वीकृति प्रदान की जाती है।
2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKUNDGARH

ISSUE TO _____

"G" Schedule

NAME OF WORK:-	वार्ड नं. 08 में अमर सिंह के घर से आर.के. स्कूल तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.84
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1680
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed within specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 8 में अमर सिंह के घर से आर.के. स्कूल तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	40.00	2.50	0.60	60.00	Cum	164.00	9840.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	40.00	2.50	0.10	10.00	Cum	2710.00	27100.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	40.00	2.50	0.10	10.00	Cum	4700.00	47000.00
								Total Amount Rs.	83940.00

Say Rs. 0.84 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.84 Lacs तक तकनीकी

स्वीकृति प्रदान की जाती है। TSN-48

2019-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 07 में सुरेश सैनी के घर से मुरारी शर्मा के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.81
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1620
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderes have must to be agreement with the office.
11. The Tenderes will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 07 में सुरेश सैनी के घर से मुरारी शर्मा के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	32.00	3.00	0.60	57.60	Cum	164.00	9446.40
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	32.00	3.00	0.10	9.60	Cum	2710.00	26016.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	32.00	3.00	0.10	9.60	Cum	4700.00	45120.00
						Total Amount Rs.		80582.40	

Say Rs. 0.81 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs.की तकनीकी

स्वीकृति प्रदान की जाती है।

Ts. N49

20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 14 में संजु जांगिड़ के घर से नागर जांगिड़ के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	1.00
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	2000
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 14 में संजु जांगीड़ के घर से नागर जांगीड़ के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	25.00	5.00	0.35	43.75	Cum	164.00	7175.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	25.00	5.00	0.10	12.50	Cum	2710.00	33875.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	25.00	5.00	0.10	12.50	Cum	4700.00	58750.00
								Total Amount Rs.	99800.00

Say Rs. 1.00 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 1.00 की तकनीकी
स्वीकृति प्रदान की जाती है।

TSN-50

13-9-19

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 16 में नत्थूसिंह के घर से चेताराम के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.98
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1960
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached singed.

Signature of Contractor.....
Address
.....
Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 16 में नत्थू सिंह के घर से चेताराम के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	30.00	4.00	0.45	54.00	Cum	164.00	8856.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	30.00	4.00	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	30.00	4.00	0.10	12.00	Cum	4700.00	56400.00
								Total Amount Rs.	97776.00

Say Rs. 0.98 Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs ...0.98...की तकनीकी
स्वीकृति प्रदान की जाती है।

T80N
51
20/9-20

OFFICE OF THE MUNICIPAL BOARD, MUKANDGARH

ISSUE TO -----

"G" Schedule

NAME OF WORK:-	वार्ड नं. 16 में कजोड़ के घर से सुल्तान के घर तक सी.सी. सड़क निर्माण कार्य
Amount of "G" schedule	0.99
Ref. of RUIDP SOR 2017	RUIDP SOR
BID Cost	500
Earnest Money	1980
Date of sale	13.09.2019 से 24.09.2019 तक दोपहर 02:00 बजे तक
Date of Receipt	25.09.2019 को दोपहर 02:00 बजे तक
completion Period	01 month

General conditions of Tender:-

1. All the Taxes whatsoever will be born by contractor.
2. Any extra if executed at site shall be paid as per RUIDP SOR-2017 rates plus or minus the tender premium.
3. Quantity of execution of item of work can be decreased increased as per the conditions of work.
4. The Work shall have to be completed with in specified time limits.
5. In case of any typographical or equivalent error in rates of "G" schedule the mentioned for the same in BSR will be treated as the correct rate.
6. Quantity control test should be carried out as per rules and instruction given by Engineer in charge all expenditure for tests should be born by contractor.
7. The successful bidder shall have to complete the works by the Intended completion Date specified in the above.
8. In order to justify their capability of execution and completion of work as per Technical Specifications.
9. The drawing and design should not be changed prior permission of competent authority.
10. The successful tenderers have must to be agreement with the office.
11. The Tenderers will be bound for follows all direction of Engineer-In charge during the executions of work.
12. The Amount of unbalance bid will be deposited before the work order.


Executive Officer
Municipal Board, Mukundgarh

Tender Rate by Tenderer

I/We hereby agree to execute the above work @% above/ below on amount of schedule "G" attached signed.

Signature of Contractor.....

Address

Email. ID

Note:- Rate Should be quoted by contractor in words and figures both rate% above/ below to the G-schedule submitted by the contractor.

Tender open by committee

Junior Engineer
Municipal Board, Mukundgarh

Accounts
Municipal Board, Mukundgarh

Executive Officer
Municipal Board, Mukundgarh

OFFICE OF THE MUNICIPAL BOARD MUKUNDGARH (JHUNJHUNU)

Detailed Estimate

Name of Work : वार्ड नं. 16 में कजोड़ के घर से सुल्तान के घर तक सी.सी. सड़क निर्माण कार्य

BASED ON BSR RUIDP SOR 2017

S.No.	item.No.	Particulars				Qty.	Unit	Rate	Amount
		Nos.	L	B	H				
1	4.10	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.							
		1	30.00	4.00	0.50	60.00	Cum	164.00	9840.00
2	9.7	Providing and laying rolled cement concrete mix of M-10 base course with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm with minimum aggregate cement ratio 15:1 and minimum cement content of 200 kg/cum, aggregate gradation to be as per table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve the designed flexural strength, finishing and curing complete as per clause 603, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion							
		1	30.00	4.00	0.10	12.00	Cum	2710.00	32520.00
3	9.5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20							
		1	30.00	4.00	0.10	12.00	Cum	4700.00	56400.00
								Total Amount Rs.	98760.00

Say Rs. 0.99Lacs

Junior Engineer
Municipal Board N Mukundgarh

Rs. 0.99Lacs की तकनीकी स्वीकृति प्रदान की जाती है। 78N 52
2019-20